Item	Description	Qty	Unit	Rate	Total (GH¢)
	DEMOLISHING WORKS				
A	Removal of defective floor tiles and dispose off site as directed by the Supervising Engineer	136	m2		
	DEMOLISHING Carried to Collection				

Item	Description	Qty	Unit	Rate	Total (GH¢)
	PLASTERWORK AND OTHER FLOOR, WALL, AND CEILING FINISHINGS				
A	600 x 600mm Porcelain floor tiles in cement grout fixed to screeded backing (m/s)	136	m2		
B	100mm high tile skirting	124	m		
	Beds and backings Cement and sand (1:3) as described on blockwork or concrete				
C	50mm thick cement sand screed laid and embedded on floor.	136	m2		
D	Patching of chiseled areas	20	m2		
E	Prepare and apply roof seal chemical with reinforced fibre for roof slab treatment	126	m2		
	MAIN BUILDING FRONT ELEVATION				
	Prepare and apply 3 coats of Acrylic Emulsion paint on Front Elevation including Priming of wall, skimming, and general Painting				
F	External wall	128	m2		

	PLASTERWORK AND OTHER FLOOR WALL AND CEI Carried to Collection ING FIN ISHI GS				

Item	Description	Qty	Unit	Rate	Total (GH¢)
	GENERAL SUMMARY				
	DEMOLISHING				
	PLASTERWORK AND OTHER FLOOR, WALL, AND CEILING FINISHINGS				
	SUB-TOTAL				
	TOTAL ESTIMATED COST				
					.